BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/17/2022-23 Dated: 15-02-2023

APPROVED TENDER SCHEDULE –'B'

Item 02

Name of Work:-Removing debris and waste materials in ward no:05 Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri B P MAHESH (M/S SRI SAI MANJUNATHA ENTERPRISES)	
				Rate	Rate in Words
1	Hydraulic Excavator of 0.9 Cum Bucket	Hr	48.00	944.00	Nine Hundred FourtyFour Only
2	1024 - Providing Tractor 40 HP Hire Charges of including Operator and Fuel	Day	346.00	1288.00	One Thousand Two Hundred EightyEight Only
3	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	1525.00	486.22	Four Hundred EightySix Paise TwentyTwo Only
4	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 5.5 m3)	Cum	144.38	334.40	Three Hundred ThirtyFour Paise Fourty Only
5	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M20 with OPC cement,with 20mm and down size graded granite metal coarse aggregate @0.70 mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work	Sqm	140.40	2072.00	Two Thousand SeventyTwo Only
6	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.km	1160.80	105.60	One Hundred Five Paise Sixty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Scanned with CamScanner